

P.O. Box 468
320 Sixth Avenue
Ouray, Colorado 81427



970.325.7211
Fax 970.325.7212
www.cityofouray.com

5th Street Water Main Replacement

PW Bid # 17-01

REQUEST FOR PROPOSALS:

Issue Date: July 24, 2017

Contact: Dennis L. Erickson, Public Works Director

Submissions Must Be Received By Tuesday August 15, 2017 at
2:00pm Colorado Time

Contact: Dennis L. Erickson, Public Works Director

Administrative

The City of Ouray is requesting formal Request for Proposals from qualified contractors through the Invitation to Bid process for replacing approximately 1,500 feet of 6 inch water main with 8 inch HDPE pipe from the intersection of 3rd Ave and 4th St. east to intersection of 3rd Ave and 5th St, then north along 5th St to the intersection of 5th St and 4th Ave., then tying back in west to the intersection of 4th Ave and 4th St., as indicated on the plan. Nine main line valves shall be included, 18 service taps with meter pits and yokes, and two fire hydrants.

A mandatory pre-bid site visit will be held on Tuesday, August 8, 2017 at the intersection of 3rd Ave. and 5th St. at 1:30 P.M.

Bids will be publicly received and registered on Tuesday, Aug 15, 2017 at City Hall, 320 6th Avenue, Ouray, Colorado 81427. Bids will be received no later than 2:00pm on the above date.

The City reserves the right to accept or reject any or all bids, to waive irregularities and/or informalities and to discard all non-conforming, non-responsive, unbalanced or conditional bids. The City of Ouray complies with all Equal Opportunity requirements. All qualified offers will receive consideration without regard to race, creed, color, national origin, sex, marital status, religion, ancestry, mental or physical handicap or age.

General

Submit signed proposals assuring a complete project. Proposals shall include enough detail showing how contractor proposes the work will be done, what equipment will be used, the expected timeline for completion and how the work will be accomplished in a timely manner which meets the City of Ouray Standards. The work shall include a traffic control plan that follows the MUTC Standards.

The City of Ouray is seeking sealed bids from qualified contactors for the project. The work shall consist of providing all the labor, equipment, material, supervision and insurance as necessary for completion of the project. Contractor shall assure public access to their homes during construction. All barricades, cones and traffic control devices shall be provided by the contractor.

SPECIAL CONDITIONS

Company Name: _____

- **PRE-BID CONFERENCE IS MANDATORY**

The mandatory Pre-Bid conference Site Visit will be held Tuesday, August 8, 2017 at 1:30 PM at the intersection of 3rd Ave and 5th St.

- **CONTACT PERSON**

For this bid the owner's representative and contact person is Dennis L. Erickson at 970 325-7074 or ericksond@cityofouray.com

- **EXISTING SITE CONDITIONS:**

The excavation will most likely encounter rocky conditions.

- **NOTIFICATIONS**

Contractor is responsible for notifying each property owner or tenant of any disruption in water service. Notifications shall be given at least the day (24 hrs) before any water is shut off. Notifications shall include expected timeline of when the water service will be shut off and expected timeline when service is turned back on. The City of Ouray will be notified at the same time of any disruption in service as well as the Fire Chief.

- **TIMELINE:**

Timeline for completion of the work is, October 20, 2017. Submit a proposed start time and completion time frame. Allow and notify the City of Ouray Public Works Director two weeks prior of anticipated start day.

- **SUBMITTAL INSTRUCTIONS:**

The City desires to receive a clear, concise, economical presentation of the vendor's proposal. Bidders should include the following information in their proposal and use the following format when compiling their responses.

- A. One (1) copy and one original of the bid packet beginning with "Special Conditions" section.
- B. Submit signed bid addendum(s)
- C. Submit a bid packet in a sealed envelope with the bid number #17-01 and project name 5th Street Water Main Replacement in the lower left hand corner of the envelope, with the bidder's name clearly written on the envelope.

Failure to submit a proposal in the manner indicated may be cause for it to be considered "non-responsive" and ineligible for consideration and subsequent award.

- **CONTRACT:**

A sample contract is attached for review and will be required prior to notice to proceed.

PROPOSAL FORM – PAGE 1

SUBMITTED BY: Company Name: _____

Address: _____ City: _____

State: _____ Zip: _____

Phone: _____ Fax: _____

CERTIFICATION: (if a Submission is Offered):

The undersigned hereby affirms that:

- He/she is a duly authorized agent of the Bidder,
- He/she has read the General Terms and Conditions, the Special Conditions and any technical specifications that were made available to the Bidder in conjunction with this Bid and fully understands and accepts these terms unless specific variations have been expressly listed on the Bid Proposal Form;
- The Bidder will accept any awards made to them as a result of this Solicitation for a minimum of ninety (90) calendar days following the date and time of the bid opening.

By: _____

Manual Signature of Agent

Date

Typed/Printed Name of Agent

Title of Agent

Include Original with Submission

Affix Manual signature of authorized agent.

NO OFFER:

Indicate reason(s) why no offer is being submitted at this time.

• **PROPOSAL FORM – PAGE 2**

Company Name: _____

Bid Item

- | | |
|--|--------------|
| 1. 1,500' 8 inch HDPE Pipe | \$ _____ |
| 2. 11- Mueller gate/wedge 300psi MJCI main line valves | \$ _____ |
| 3. 11- screw adjustable valve boxes for main line valves | \$ _____ |
| 4. 2- Mueller Super Centurion 250TM | |
| 5 ¼ barrel Fire Hydrants | \$ _____ |
| 5. 18- Mueller BR Series water tap saddles | \$ _____ |
| 6. 18- ¾ inch HM meter yokes with check valve | \$ _____ |
| 7. 18- ¾ inch Mueller water service corporation valves | \$ _____ |
| 8. Pipe bedding material | \$ _____ |
| 9. Locating wire and warning tape | \$ _____ |
| 10. Traffic control | \$ _____ |
|
Project Total: NOT TO EXCEED |
\$ _____ |

PROMPT PAYMENT TERMS:

Discount: _____ % _____ Days

Net: _____ Days

VARIATIONS:

The bidder shall identify all variations and exceptions taken to the general terms and conditions, the special conditions in the space provided below.

Page # _____ Item # of Section: _____

Variance

Page # _____ Item # of Section: _____

Variance

STATEMENT OF WORK

The City of Ouray is seeking Request for Proposals from qualified contractors to replace approximately 1,500 feet of 6 inch water main with 8 inch HDPE pipe from the intersection 3rd Ave and 4th St. east to intersection of 3rd Ave and 5th St, then north along 5th St to the intersection of 5th St and 4th Ave., then tying back west to the intersection of 4th Ave and 4th St. as indicated on the plan. Included are nine main line valves, 18 water service taps with meter pits and yokes and two fire hydrants.

All work shall comply with the City of Ouray Infrastructure Standards with special attention given to Chapters 2, 3 & 7.

The main line and service taps shall be buried a minimum of 5 foot at the top of the pipe with 12 inches of city approved bedding material under the pipe and 12 inches above the pipe. Water line warning tape shall be installed on top of the 12 inches of bedding material prior to backfilling. 10 gauge direct bury high flex tracer wire will be taped to the

top of the pipe every 2 feet and brought up inside the screw adjustable main line valve boxes.

The 18 water service line pipes shall be high density polyethylene Pure-Core C901 PE pressure pipe rated for high pressures.

It is the contractor's responsibility to notify the property owner or tenant of disruption in water service and to notify them the day of the proposed service tap connections work. The City of Ouray shall be notified of all water shut offs or road closures.

Contractor is responsible for notification to all emergency service should any road closure be necessary. This includes police department, fire department and EMS services.

All water service shall be turned back on at the end of each day's work. All trenches shall be backfilled, compacted or plated at the end of the work day and only after inspection by a City of Ouray representative.

Proper disinfection and flushing of the main lines shall be completed before connections are made for domestic use. Chlorine residuals shall be taken, recorded, and documented before and after to assure proper disinfection with a copy provided to the City of Ouray.

Proper compaction shall be done with the streets graveled with class 6 road base at the completion of the excavation work and before final acceptance of completion.

The work shall consist of providing all the labor, equipment, traffic control, material and supervision as necessary to furnish and install the water main, service taps and fire hydrants as per the City Specifications and the statement of work.

It is the City of Ouray's desire to have all USA American made pipe and fittings. All fittings shall be lead free.

Upon completion of the work and before final payment is made, as built plans shall be provided electronically along with two hard copies.